BHARAT SANCHAR NIGAM LIMITED
(A Government of India Enterprise)

BID DOCUMENT

For the work of

Day to day maintenance works in TE compound at Haldwani, Nainital for four months.

NIT No: 19/NIT/EE(C)/BSNL/HLW/2026-27

Certified that this document contains 38 (Thirty Eight) printed pages including the cover page.

To be submitted only online on the website:etenders.gov.in

By 18:00 Hrs. on 09.11.2026

Executive Engineer (C),
BSNL Civil Division,
Haldwani

Name of work : Day to day maintenance works in TE compound at Haldwani, Nainital for four months.

INDEX

S. No.	Details	Page No.	
		From	To
1	Index	2	2
2	Information And Instructions For Bidders For e-Tendering	3	3
3	BSNL W – 6 (Notice Inviting E-Tender)	4	9
4	BSNL W – 8 (Abridged Version)	10	11
5	Performa of “Tender Acceptance Letter” with Annexure-A	12	13
6	Performa of ANNEXURE-I to V	14	14
7	Performa of Schedules	15	18
8	Additional Conditions	19	23
9	Additional Specifications	24	31
10	Special Conditions for the work	32	35
11	Performa for Guarantee Bond for Water proofing	36	36
12	Preferred list of various items/Products	37	37
13	Schedule of Quantity	38	46

INFORMATION AND INSTRUCTIONS FOR CONTRACTORS / BIDDERS FOR E-TENDERING FORMING PART OF BID DOCUMENT AND TO BE POSTED ON WEBSITE

1. The intending bidder must read the terms and conditions of BSNL-W6 & 8 as per this document and General Conditions of Contract, as available on website www.civil.bsnl.co.in. He should only submit his bid if he considers himself eligible and he is in possession of all the documents required.
2. Information instructions for bidders posted on website shall form part of the bid document.
3. The bid document consisting of plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents can be seen and downloaded from website **etenders.gov.in or www.tender.bsnl.co.in** free of cost.
4. **Submission of Documents:**
   a) **If the bidder is an individual, bid documents shall be signed by him above his full type written name and current address.**
   b) **If the bidder is a proprietary firm, bid documents shall be signed by the proprietor above his full typewritten name and the full name of his firm with its current address.**
   c) **If the bidder is a firm in partnership, bid documents shall be signed by all the partners of the firm above their full typewritten names and current addresses, or, alternatively, by a partner holding power of attorney for the firm. In the later case a certified copy of the power of attorney should accompany the application. In both cases a certified copy of the partnership deed and current address of all the partners of the firm should accompany the application.**
   d) **If the bidder is a limited company or a corporation, bid documents shall be signed by a duly authorized person holding power of attorney for signing the application accompanied by a copy of the power of attorney. The bidder should also furnish a copy of the Memorandum of Articles of Association duly attested by a Public Notary.**
5. Those bidders not registered on the website mentioned above, are required to get registered beforehand. If needed, they can be imparted training on online bidding process as per “Instructions to bidder for online bid submission” available on the website downloads section.
6. The intending bidder must have valid class-III digital signature to submit the bid.
7. On opening date, the contractor can login and see the bid opening process. After opening of bids hewill receive the competitor bid sheets.
8. Contractor can upload documents in the form of **JPG** format and **PDF** format.
9. Contractor must ensure to quote rate of each item. Therefore, if any cell is left blank and no rate is quoted by the bidder, rate of such item shallbe treated as **"0" (ZERO).**
10. The envelope 1 of online bid containing Eligibility Credentials (Technical Bid) shall be opened first. The time and date of opening of online financial bid of contractors qualifying the Eligibility Credentials shall be communicated to them on a later date.
11. Conditional tender shall be rejected.
12. Pre-Bid conference shall be held in the chamber of **Executive Engineer (C), BSNL Civil Division, Haldwani** at 15.00 Hrs. on dated **05.11.2026** to clear the doubts of intending bidders, if any.
13. The department reserves the right to reject any prospective application without assigning any reason and to restrict the list of qualified contractors to any number deemed suitable by it, if too many bid sare received satisfying the laid down criteria.
14. The tenderer should read carefully & understand the tender document, procedure for e-tendering etc. completely before participating in the e-tender procedure. Participation in the e-tendering presumes that the bidder(s) has/have read all the conditions, Special Conditions of the Contract, Schedule of Quantity etc. and is agreed with & shall abide by them.
15. If the contractors do not submit the physical bid documents/Technical Bid consecutively three times after submission of online bids, action shall be taken to withdraw his/their enlistment & debar him/them from tendering in BSNL for the period of six months. An undertaking in this regard is to be submitted along with the tender by the tenderers as per Annexure III.

BHARAT SANCHAR NIGAM LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
EXECUTIVE ENGINEER (CIVIL), BSNL CIVIL DIVISION, Haldwani

NOTICE INVITING e-TENDER

NIT No. 19/NIT/EE(C)/BSNL/HLW/2026-27 Dated: 27.10.2026

Executive Engineer (C), BSNL Civil Division, **Haldwani** on behalf of Bharat Sanchar Nigam Limited (A Government of India Enterprise) invites online item rate(inclusive of all taxes, levies and GST as per GOI Guidelines)bids on **two bid system** from approved and eligible contractors of DOT/ BSNL Civil Wing and those of Uttarakhand State PWD (Building works only), DOP, CPWD, MES and Railways, having valid EPF registration & GST registration for the following work:

S. No.	Name of Work & Location	Estimated Cost put to bid	Earnest money	Period of Completion	Last date and time of submission of online bid	Time & Date of Opening of "Online Technical Bid"	Last Date & Time of submission of "Physical Bid Documents"
1	2	3	4	5	6	7	8
1	**Day to day maintenance works in TE compound at Haldwani, Nainital for four months.**	**Rs. 2,49,631/-**	**Rs. 4,993/-**	**04(Four) months**	**Up to 18:00 Hrs 09.11.2026**	**15:30 Hrs on 12.11.2026**	**On any date before or within 5 days of bid submission end date, i.e. up to 15:00 Hrs. on 16.11.2026**

1.2 Eligibility Criteria: Work experience criteria for eligibility for issue of tender documents for non BSNL registered contractors of public works organizations like CPWD, Uttarakhand State PWD (Building works only), DOP, MES and Railways only:

1.2.1 The applicant should have completed works as per details below in Central Government / State Government/ Central PSU / State PSU during the last seven years ending last day of the month previous to the one in which the tenders are invited:

a) Three similar completed works each costing not less than **NIL**

b) Two similar completed works each costing not less than **NIL**

c) One similar completed works each costing not less than **NIL**

Similar work shall mean "Building Maintenance Works"

1.2.2 The works done for Central Government / State Government / PSU shall only be considered for eligibility, provided they submit definite proof from the appropriate authority, not below the rank of Executive Engineer of having satisfactorily completed similar works of magnitude specified above.

1.2.3 The work done certificate shall be considered as invalid, if Extension of Time (EOT) is granted with levy of compensation or not decided on the last date of submission of bid.

1.2.4 The experience certificate given shall indicate clearly, the name &nature of the work, agreement no. and satisfactory completion of the work along with actual value of work done and stipulated/ actual date of completion and shall be issued by authorized signatory/ authority and shall be uploaded on website & also physically submitted in original/ attested.

1.2.5 Copies of work order/ work award letters will not be acceptable.

1.2.6 The value of the executed works shall be brought to current costing level by enhancing the actual value of work at simple rate of 7% per annum; calculated from the date of completion to last date of receipt of applications for tenders and shall be rounded off to the nearest hundred rupees.

1.3 The contractor shall have to fully abide by the relevant provisions of the Employee's Provident Fund Act 1952, ESIC (wherever applicable) and Rules of The Employee's Provident Funds Act / Scheme 1961 (as applicable) framed therein from time to time and shall have to obtain and produce EPF/ ESIC registration within one month from the date of receipt of award letter or before release of any payment by BSNL, whichever is earlier

1.4 The agency/agencies, which are Blacklisted/Debarred/Ceased for Financial Transactions by BSNL and/or any Central/ State Govt. Department/PSU are not eligible for tendering.

2.0 Agreement shall be drawn with the successful Tenderer on prescribed Form No. BSNL W-8 with up to date Correction slips, which is available as a BSNL Publication in the office of the Executive Engineer (C), BSNL Civil Division, Haldwani / BSNL Web site www.civil.bsnl.co.in. Tenderer shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.

3.0 The time allowed for carrying out the work will be **04(Four) months** from the 10th (Tenth) day after the date of issue of letter of award of work, or, from the first day of handing over of the site, whichever is later.

4.0 The site for the work is **Main TE building compound, Haldwani.**

5.0 The contractor can revise the rate of one or more item(s) any number of times (he need not re-enter rate of all the items) but before last time and date of submission of online bid as notified.

6.0 **Submission of Tenders:** Interested contractor who wish to participate in the tender has to make the following payments and the details of which is to be filled up/ uploaded online along with other documents as per bidin Eligibility Credentials (Technical Bid) part on e-tender portal (1st electronic Envelope)within the period of bid submission:

6.1 Tender fee & Earnest Money Deposit:-

a) **Tender fee:** Tender fee is required to be deposited by the bidder amounting to **Rs.590/- (Rupees Five Hundred Ninety)** only i/c GST as cost of tender (Non refundable) in cash or demand drafts/pay orders of a schedule bank drawn in favour of **AO(Cash), BSNL, O/o The GMT, Nainital BA** or through online payment mode (RTGS/NEFT).

Earnest Money: Earnest Money of **Rs. 4,993/- (Rupees Four Thousand Nine Hundred Ninety Three) only** in the form of deposit at Call receipt of a scheduled bank / fixed deposit receipt of a scheduled bank / demand draft of a scheduled bank issued in favour of **AO(Cash), BSNL, O/o The GMT, Nainital BA** or through online payment mode (RTGS/NEFT).

a) Tender fee & Earnest Money Deposit shall preferably be submitted by bidder through online payment mode (RTGS/NEFT) as per following bank details:

Name of Bank Account Holder: **Account Officer (Cash)**
Bank Account No: **0196002100036208**
IFSC code: **PUNB0019600**
Name of the Bank and Branch Address: **Punjab National Bank, Main Branch, Nainital Road, Haldwani**

If bidder opts DD/Banker's cheque/FDR for EMD then scanned copy of the payment instrument be uploaded in their online technical bid part on e-tender portal and in that case original payment instrument must be deposited in the office of Executive Engineer (C), BSNL Civil Division, Haldwani along with **"Physical Bid documents"**.

b) If bidder opts online payment mode then scanned copy of Bank Transaction details with UTR number towards the successful e-payment (RTGS/NEFT) for tender fee/EMD be uploaded in their online technical bid part on e-tender portal and a certified copy of same must also be deposited in the office of Executive Engineer (C), BSNL Civil Division, Haldwani along with **"Physical Bid documents"**.

6.2 MODE OF SUBMISSION:

a) Certificate of work experience and other documents as specified in the NIT shall be scanned and uploaded online as **Eligibility Credentials (Technical Bid)** part on e-tender portal (**1st electronic Envelope**)within the period of bid submission. **During tender process, the bidder may be required to produce original copy of any documents, submitted as scanned copy online in 1st electronic Envelope, which the bidder will have to comply with.**

b) Original Payment Instruments/ Cash receipt or certified copy of Bank Transaction details towards the successful e-payment against EMD and cost of Bid Document, shall be placed in single wax/adhesive tape sealed envelope superscripted as **"Physical Bid documents"** with name of work, name of tenderer, due date & time of opening of bids and shall be submitted in the office of Executive Engineer (C), BSNL Civil Division, Haldwani **on any date before or within 5 days of bid submission end date, i.e. up to 15:00 Hrs. on 16.11.2026.** Failing which the already opened online technical bid of the bidder (documents scanned and uploaded to the e-tendering website within the period of bid submission) shall be rejected.

7.0 The **"Online Technical Bid"** shall be opened at **15.30 Hrs.** on **12.11.2026.** The **online financial bids** shall be opened only for those tenderers, whose eligibility documents are found in order and are valid. The date and time of opening of **online financial bid** shall be as mentioned in the bid or shall be communicated at a later date. The bid submitted shall become invalid and cost of bid shall not be refunded if:

(i) The bidder is found ineligible.

(ii) The bidder does not upload scanned copies of all the documents as specified in the bid document.

(iii) If any discrepancy is noticed between the documents as uploaded at the time of submission of online bid and hard copies as submitted physically in the office of tender opening authority. **In such case, the bidder will also be suspended for participation in the tendering process for the works of BSNL for a period of one year from the date of issue of such order of suspension.**

8.0 Copies of other drawings and documents pertaining to the work will be open for inspection by the tenderers at the office of the Executive Engineer (C), BSNL Civil Division, **Haldwani.**

9.0 Tenderers are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their tenders as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general, shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their tender. A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charges consequent on any misunderstanding or otherwise shall be allowed. The tenderer shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity, access facilities for workers and on all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of tender by a tenderer implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done and local conditions and other factors having a bearing on the execution of the work.

10.0 The competent authority on behalf of Bharat Sanchar Nigam Limited does not bind himself to accept the lowest or any other tender, and reserves to himself the authority to reject any or all of the tenders received without the assignment of a reason. All tenders, in which any of the prescribed conditions is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer, shall be summarily rejected.

11.0 Canvassing whether directly or indirectly, in connection with tenders is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.

12.0 The competent authority on behalf of the Bharat Sanchar Nigam Limited reserves with himself the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the rate quoted.

13.0 The company or firm or any other person shall not be permitted to tender for work in BSNL Civil Zone in which his near relative(s) (directly recruited or on deputation in BSNL) is/are posted in any capacity either non-executive or executive employee. Near relative(s) for this purpose is/are defined as:-

(i) Member of Hindu Undivided family (HUF).
(ii) They are Husband and Wife.
(iii) The one is related to other in the manner as Father, Mother, Son(s), & Son's wife (daughter-in-law), Daughter(s), Daughter's husband (son-in-law) Brother(s), Brother's wife, Sister(s), Sister's husband (brother-in-law).

The contractor shall also intimate the names of persons who are working with him in any capacity or are subsequently employed by him and who are near relative to any executive employee / Gazetted officer in the BSNL or Department of Telecom or in the Ministry of Communications.

All the intending tenderers will have to give a certificate that none of his/her such near relative(s) as defined above is/are working in the concerned BSNL Civil Zone where he is going to apply for tender / work. The format of the certificate is as under:

"I……S/o Shri……Resident of……hereby certify that none of my relative(s) as defined in BSNL W-6 at SI. No. 13.0, is/are employed in BSNL Uttarakhand Civil Zone. In case at any stage, it is found that the information given by me is false / incorrect, BSNL shall have the absolute right to take any action as deemed fit without any prior intimation to me."

The certificate in case of Proprietorship Firm shall be given by the proprietor, for Partnership Firm certificate shall be given by all partners and in case of Limited Company, by all Directors of the company. However, Government of India / Financial Institutions nominees and independent non-official part-time Directors appointed by Govt. of India or the Governor of the State are excluded from the purview of submission of this certificate while submitting tenders by Limited Companies.

Any breach of these conditions by the Company or Firm or any other person, the Tender / work will be cancelled and Earnest Money / Security Deposit will be forfeited at any stage, whenever it is so noticed. BSNL will not pay any damages to the Company or Firm or the concerned person but damages arising on account of such cancellation to be borne by the contractor. The Company or Firm or the person will also be debarred for further participation in the tender in the concerned BSNL Civil Zone. Further, any breach of this condition by the tenderer would also render him liable to be removed from the approved list of contractors of BSNL. If however the contractor is registered in any other Department he shall also be debarred from tendering in BSNL for any breach of this condition.

14.0 No Engineer of Gazetted / Executive rank or other Gazetted Officer/Executive employed in engineering or administrative duties in an Engineering Department of the Government of India/State Government or BSNL is allowed to work as a contractor for a period of two years after his retirement from Govt. service, without previous permission of the Govt. of India or BSNL in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Govt. of India/ State Government or BSNL as aforesaid before submission of the tender or engagement in the contractor's service.

15.0 The tender for the work shall remain open for acceptance for a period of **30 (Thirty) days** from the last date of opening of financial bid. If any tenderer withdraws his tender before the said period or issue of letter of acceptance/intent, whichever is earlier, or, makes any modifications in the terms and conditions of the tender which are not acceptable to the BSNL, then the BSNL shall, without prejudice to any other right or remedy, be at liberty to forfeit 50% of the said earnest money as aforesaid.

16.0 For work costing more than 15 Lac, the successful tenderer shall, upon issue of letter of acceptance of tender, shall be required to furnish Performance Guarantee **@ 5%** of the tendered

value in the form of irrevocable Bank Guarantee of requisite amount to the Engineer-in-charge in the Performa annexed to the tender document, within 15 days of the issue of letter of acceptance of tender by the BSNL. In the event of failure on the part of the successful tenderer to furnish the Bank Guarantee within 15 days, the earnest money will be forfeited and tender cancelled.

17.0 This Notice Inviting Tender (BSNL W-6) shall form a part of the Contract Document. In accordance with Clause-1 of the contract, the letter of acceptance shall be issued first in favour of the successful Tenderer / Contractor. After submission of the performance guarantee, the letter of award shall be issued. The Contract shall be deemed to have come in to effect on issue of letter of acceptance of the tender. On issue of letter of award, the successful Tenderer / Contractor shall, within 15 days from such date, formally sign the agreement consisting of :-

a) The Notice Inviting Tender, all the documents including additional conditions, specifications, special conditions, etc. and drawings, if any, forming part of the tender, and, as issued at the time of invitation of tender and acceptance thereof together with any correspondence leading thereto.

b) Standard BSNL W-8 with up to date Correction Slips as on website www.civil.bsnl.co.in.

c) Agreement signed on non-judicial stamp paper as per Performa annexed to the tender document.

18.0 Payment to the contractors shall be made through e-payment system like ECS & EFT as detailed below:-

(a) In cities / areas where ECS / EFT facility is provided by Banks, the tenderer must have Account in such ECS / EFT facility providing Bank and that Bank A/C no shall be quoted in the tender by the tenderer.

(b) The cost of ECS / EFT will be borne by BSNL in all cases where the payment to contractor is made in a local branch i.e. tenderer is having bank account in the same place from where the payment is made by BSNL unit.

(c) In case payment is made to outside branch i.e. tenderer is having bank account not in the same place from where the payment is made by BSNL unit, the crediting cost will have to be borne by the tenderer only.

(d) The payments to contractors will compulsorily be made through ECS / EFT in respect of all contracts where the value of the contract is more than -*-.

19.0 First running account bill shall be paid only after

(a) Signing of the Agreement / Contract by both the parties, and

(b) Progress chart has been prepared as required under Clause 5 and approved by the competent authority.

20.0 General conditions of contract 2006 with upto date Correction Slips for works in BHARAT SANCHAR NIGAM LIMITED are available on website www.civil.bsnl.co.in as well as in the Divisional office.

List of Documents to be scanned and uploaded online as Eligibility Credentials (Technical Bid) part on e-tender portal (1st electronic Envelope) within the period of bid submission:

i. Tender Acceptance Letter along with Annexure-A (as per Performa enclosed)

ii. Demand draft/Pay order of any Scheduled Bank towards cost of Bid document. [Copy of Bank transaction details with UTR number, if bidder deposits cost of Bid documents online.]

iii. Deposit at Call receipt of a scheduled bank / fixed deposit receipt of a scheduled bank / demand draft of a scheduled bank towards EMD. [Copy of Bank transaction details with UTR number, if bidder deposits EMD online.]

iv. Copy of PAN Card

v. Valid Enlistment order of the contractor

vi. ANNEXURE-I: Certificate for near Relatives *(Note: The certificate in case of Proprietorship Firm shall be given by the proprietor and for Partnership firm's certificate shall be given by all Partners and in case of Limited Company by all Directors of the company)*

vii. Copy of Employee Provident Fund Registration & ESIC Registration *. If the bidder has not obtained EPF/ ESIC Registrations then in such a case the bidder shall scan and upload undertaking as per Annexure-II.

viii. Undertaking as per Annexure-III (Regarding Submission of Physical Bid Documents)

ix. Copy of valid GST registration certificate, if already obtained by the bidder. If the bidder has not obtained GST registration as applicable, then he shall scan and upload undertaking as per Annexure-IV.

x. Work experience certificates, if required.

xi. Power of attorney/ authorization to the person who signs the tender.

xii. For partnership firms, partnership deed with current address of all the partners of the firm.

xiii. For Limited Company or Corporation, a copy of the Memorandum of Articles of association duly attested by a Public Notary.

Executive Engineer (C),
BSNL Civil Division,
Haldwani

BHARAT SANCHAR NIGAM LIMITED

(A Government of India Enterprise)

ABRIDGED FORM BSNL W-8

STATE :	**Uttarakhand**	**CIRCLE**	**: UTTARAKHAND**
ZONE :	**Uttarakhand Civil Zone**	**DIVISION**	**: Haldwani**
		SUB-DIVISION	**: Haldwani-I**

Item Rate Bid & Contract for Work

Item rate Bid for the work of: Day to day maintenance works in TE compound at Haldwani, Nainital for four months.

(i) To be submitted online on the website etenders.gov.in by 18:00 hours on dated **09.11.2026.**

(ii) The **"Online Technical Bid"** shall be opened at **15:30** hours on dated **12.11.2026** in the presence of bidders who may be present in the office of **Executive Engineer (C), BSNL Civil Division, Haldwani.**

(iii) Envelope marked **"Physical Bid Documents"** to be submitted by **15:00** hours on dated **16.11.2026.**

(iv) **Financial Bid** to be opened in the presence of bidders who may be present, at a date & time to be communicated later on, in the office of **Executive Engineer (C), BSNL Civil Division, Haldwani.**

T E N D E R

I/We have read and examined Notice Inviting Tender, Schedules A, B, C, D, E & F, Specifications applicable, Drawings & Design, General Rules and Directions, Conditions of Contract, clauses of contract, Special conditions, Schedule of Rate & other documents & Rules referred to in the Conditions of contract and all other contents in the Tender Document for the work.

I / we hereby tender for the execution of work specified for the Bharat Sanchar Nigam Limited within the time specified in schedule 'F' viz., schedule of quantities and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule-1 of General Rules and Directions (Civil and Electrical) and in Clause 11 of the Conditions of the contract and with such materials as are provided for, by and in respect in accordance with, such conditions so far as applicable.

I/We agree to keep the tender open for **30 (Thirty) days** from the date of opening of financial bid thereof and not to make any modifications in its terms and conditions. If I/we withdraw my/our tender before the said period or issue of letter of acceptance/intent, whichever is earlier, or, makes any modifications in the terms and conditions of the tender which are not acceptable to the BSNL, then the BSNL shall, without prejudice to any other right or remedy, be at liberty to forfeit 50% of the said earnest money as aforesaid.

If I/We fail to commence the work specified I/We agree that the said Bharat Sanchar Nigam Limited shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely otherwise the said earnest money shall be retained by competent authority on behalf of the Bharat Sanchar Nigam Limited towards Security Deposit to execute all the works referred to in the tender documents upon the terms and conditions contained or referred to therein and carry out such deviations as may be ordered, upto maximum of the percentage mentioned in Schedule 'F' and those in excess of that limit at the rates to be determined in accordance with the provision contained in Clause 12.2 and 12.3 of the tender form.

I/We agree that, in case of works of estimated cost exceeding Rs.15,00,000/-, to deposit an amount equal to **5%** of Tendered value of the work as performance guarantee in the form of bond of any Scheduled Bank of India in accordance with the Performa prescribed or in the form of Fixed Deposit Receipt etc., within 15 days of the issue of letter of acceptance of Tender by the BSNL. I/We am/are aware that in the event of failure on my/our part to furnish the Bank Guarantee within 15 days, the earnest money will be forfeited and tender cancelled.

I/we hereby intimate that for receiving payments I/we have an account in _____ Bank with account No. _____ where the ECS/EFT/RTGS facility of e-payment is available.

I/We hereby declare that I/we shall treat the tender documents, drawings and other records connected with the work as secret/ confidential documents and shall not communicate information derived there-from to any person other than a person to whom I/we am/are authorized to communicate the same or use the information in any manner prejudicial to the safety of the State.

I / We agree that should I / we fail to commence the work specified in the above memorandum, an amount equal to the amount of the earnest money mentioned in the form of invitation of tender shall be absolutely forfeited to the Bharat Sanchar Nigam Limited and the same may at the option of the competent authority on behalf of the Bharat Sanchar Nigam Limited be recovered without prejudice to any right or remedy available in law out of the deposit in so far as the same may extend in terms of the said bond and in the event of deficiency out of any other money due to me / us under this contract or otherwise.

The information in respect of works in hand is as per Performa enclosed.

"I/we agree that this contract is subject to jurisdiction of Court at Haldwani only."

Dated: ……..
Witness: ……..
Address: ……..
Occupation: ……..

Signature of Contractor
Postal Address: -

ACCEPTANCE

The above tender (as modified by you (Contractor) and as provided in the letters mentioned hereunder) is accepted by me on behalf of the **Bharat Sanchar Nigam Limited** for a sum of Rs. ……(Rupees …… ……..)

The letters referred to below shall form part of this contract Agreement: -

a) ……

b) ……

On behalf of the Bharat Sanchar Nigam Limited

Signature
Executive Engineer (C),
BSNL Civil Division,
Haldwani
Dated ……

TENDER ACCEPTANCE LETTER

(To be given on Company Letter Head)

No. …… Date:

To,

The Executive Engineer (C),
BSNL Civil Division,
Haldwani

Sub: Acceptance of Terms & Conditions of Tender

Name of Work: Day to day maintenance works in TE compound at Haldwani, Nainital for four months.

E-TENDER NOTICE NO: 19/NIT/EE(C)/BSNL/HLW/2026-27

Dear Sir,

1. I am /we are registered as **Individual/ Sole Proprietor/ Partnership Firm/ Company** with **BSNL Civil Wing/ DOT/specialized agency……** (Fill name of deptt), as **Class……** contractor(s) and my/ our **registration number is ……**It is certified that as on date the said registration is **valid up-to ……..**
2. I / We have downloaded / obtained the tender documents for the above-mentioned work from the website **etenders.gov.in /**or **www.tender.bsnl.co.in** as per your advertisement therein.
3. I / We hereby certify that I / we have read the entire terms and conditions of the tender documents(including Information and Instructions for Bidders for e-Tendering, Notice Inviting E-Tender, BSNL W – 8, Performa of Schedules, General Conditions of Contract, Additional Conditions/ Specifications, Special conditions Specifications, if any, and annexure, schedules, etc),which form part of the contract agreement and I / we shall abide by the terms/ conditions/ clauses contained therein.
4. The corrigendum issued from time to time by your department/ organisation has also been taken into consideration, while quoting rates & submitting the bid.
5. I / We hereby unconditionally accept the tender conditions of above-mentioned tender document(s) / corrigendum(s) in its totality / entirety.
6. I / We do hereby declare that our Firm has not been blacklisted/ debarred by any Govt. Department/Public sector undertaking.
7. I /We have uploaded scanned copies of all necessary documents along with the bid within the period of bid submission. The “Physical Bid Documents” as per NIT conditions are hereby submitted in hard copy as per Annexure-A enclosed.
8. I / We certify that all information furnished by the me/ our Firm is true & correct and, in the event, that the information is found to be incorrect/ untrue or found violated, then BSNL shall without giving any notice or reason therefore or summarily reject the bid or terminate the contract, without prejudice to any other rights or remedy including the forfeiture of the full said earnest money deposit absolutely.

Yours Faithfully,

Signature of the authorised signatory with Official Seal
Address:……
……
Phone Nos: ……
E-MAIL ID:……

E-TENDER NOTICE NO : 19/NIT/EE(C)/BSNL/HLW/2026-27
Name of Work: **Day to day maintenance works in TE compound at Haldwani, Nainital for four months.**
Name of Tenderer:

Sl. No.	List of Documents to be scanned and uploaded within the period of bid submission:	Whether uploaded online (Yes/No)	Hard copy (Physical Bid) enclosed with this letter (Yes/No)
i.	DD / Pay order of a scheduled bank towards Cost of Bid Documents or Copy of Bank transaction details with UTR number (For Online Payments)		
ii.	Deposit at Call receipt of a scheduled bank / fixed deposit receipt of a scheduled bank / demand draft of a scheduled bank towards EMD or Copy of Bank transaction details with UTR number (For Online Payments)		
iii.	Copy of PAN Card		NA
iv.	Copy of Valid Enlistment Order		NA
v.	ANNEXURE-I: Certificate for Near Relatives		NA
vi.	Copy of EPF & ESIC Registration Certificate or Undertaking as per Annexure-II		NA
vii.	Undertaking as per Annexure-III (Regarding Submission of Physical Bid Documents)		NA
viii.	Copy of Certification of Valid Registration for GST or Uundertakings as per Annexure-IV		NA
ix.	Work Experience Certificate for non BSNL Registered Contractors		NA
x.	Power of attorney/ authorization to the person who signs the tender.		NA
xi.	For partnership firms, partnership deed with current address of all the partners of the firm		NA
xii.	For Limited Company or Corporation, a copy of the Memorandum of Articles of Association duly attested by a Public Notary		NA

*(NA- Not Applicable)

(Signature of the Bidder, with Official Seal)

Proforma of Annexure I to V

ANNEXURE-I
CERTIFICATE FOR NEAR RELATIVES

(Note: The certificate in case of Proprietorship Firm shall be given by the proprietor and for Partnership firm's certificate shall be given by all Partners and in case of Limited Company by all Directors of the company)

I……S/o Shri……..Resident of……hereby certify that none of my relative(s) as defined underpara 13.0 of Notice Inviting E-Tender, is/are employed in BSNL Uttarakhand Circle. In case at any stage, it is found that the information given by me is false / incorrect, BSNL shall have the absolute right to take any action as deemed fit without any prior intimation to me.

Sign of Contractor (Authorized Signatory)

ANNEXURE-II
DECLARATION REGARDING EPF, ESIC & LABOUR LICENSE

I / We _____ do hereby solemnly declare that I shall abide by all the rules/conditions/provisions of 'The Employees Provident Funds Act / Scheme 1961' and ESIC Act. I/We shall obtain and submit applicable EPF, Labour License & ESIC within one month from the date of receipt of award letter or before release of any payment by BSNL, whichever is earlier. In case of any default, the sole responsibility shall be mine/us. I/We shall also be liable for any pecuniary liability arising on account of any violation by me/us of the provisions of the said Acts.

This declaration shall become part of the Agreement.

Sign of Contractor (Authorized Signatory)

ANNEXURE-III
UNDERTAKING REGARDING SUBMISSION OF PHYSICAL BID DOCUMENTS

If I/We _____ do not submit the physical bid documents/Technical Bid consecutively three times after submission of online bids, it shall be treated as breach of conditions and action shall be taken to withdraw my/our enlistment/debar me/us from tendering in BSNL for six months.

Sign of Contractor (Authorized Signatory)

ANNEXURE-IV
UNDERTAKING REGARDING SUBMISSION OF GST REGISTRATION CERTIFICATE

If work is awarded to me, I/we shall obtain GST registration certificate, as applicable, within one month from the date of receipt of award letter or before release of any Payment by BSNL, whichever is earlier, failing which I/we shall be responsible for any delay in payments which will be due towards me/us on account of the work executed and/or for any action taken by BSNL or GST department in this regard

Sign of Contractor (Authorized Signatory)

PROFORMA OF SCHEDULES

SCHEDULE "A"

"Schedule of Quantities" - Enclosed

SCHEDULE "B"

Schedule of Materials to be issued to the contractor

S. No	Description of Item	Quantity	Rates in figures & words at which the materials will be charged from the contractor	Place of issue
1	2	3	4	5
----------NIL----------				

SCHEDULE "C"

Tools and Plants to be hired to the contractor

S. No.	Description of Item	Hire charges per day	Place of issue
1	2	3	4
----------NIL----------			

SCHEDULE "D"

General Instructions, list of preferred makes to be used for this work, Special Conditions. Enclosed.

SCHEDULE "E"

Schedule of component of Materials, Labour etc for escalation

Component of Materials expressed as percent of Total Value of Work	**"X"**	**Not applicable**
Component of Labour expressed as percent of Total Value of Work	**"Y"**	
Component of POL expressed as percent of Total value of Work	**"Z"**	

SCHEDULE "F"

Reference to General Conditions of Contract

Name of Work	**Day to day maintenance works in TE compound at Haldwani, Nainital for four months.**
Estimated cost of Work	**Rs. 2,49,631/- (Rupees Two Lakh Forty Nine Thousand Six Hundred Thirty One) only**
Earnest Money	**Rs. 4,993/- (Rupees Four Thousand Nine Hundred Ninety Three) only**
Performance Guarantee (**5%**of the tendered value in the form of Bank Guarantee from Schedule bank in respect of work with estimated cost put to tender exceeding Rs.15 Lakhs)	Rs._____(Rupees_____ _____ _____only)
Security Deposit (10 % of the tendered value (subject to a maximum of Rs.5 Lakh) in respect of work with estimated cost put to tender up to Rs.15.0 Lakhs and @ 5 % of the tendered value (subject to a maximum of Rs.2.5 Lakhs) in respect of work with estimated cost put to tender above Rs.15.0 Lakhs	Rs._____(Rupees_____ _____ _____only)

GENERAL RULES AND DIRECTIONS		
Officers inviting tender		**Executive Engineer (C), BSNL Civil Division, Haldwani**
Definitions		**See below**
2(v)	Engineering in Charge	**Executive Engineer (C), BSNL Civil Division, Haldwani**
2(viii)	Accepting Authority	**Executive Engineer (C), BSNL Civil Division, Haldwani**
2(x)	Percentage on cost of materials and Labour to cover all overheads and profit	**10 %**
2(xi)	Standard Schedule of Rates	**CPWD Delhi Schedule of Rates 2023 with upto date correction slips.**
9(ii)	Standard BSNL Contract Form	**BSNL W-8 form as modified and corrected up to date Correction Slips No.1 to 4 & 6.**
Clause 2		
Authority for fixing compensation under Clause 2		**Executive Engineer (C), BSNL Civil Division, Haldwani**
Whether Clause 2 A applicable.		**No**
Clause 3A		
Whether Clause 3 A applicable.		**No**
Clause 5		
i)	Time allowed for execution of work.	**04(Four) months**
Ii)	Authority to give fair and reasonable extension of time for completion of work.	**Executive Engineer (C), BSNL Civil Division, Haldwani**
Clause 6A		
Whether Clause 6A shall be applicable?		**Yes**
Clause 7		
Gross value of work to be done together with net payment /adjustment of advances for materials collected, if any, since the last such payment for being eligible to interim payment.		**Rs. 1.85 Lakhs**
Clause 10		
Reinforcement steel to be used in the work shall have to be procured as below :		**TMT Bars confirming to IS 1786:2008,from main producers as approved by the Ministry of steel like SAIL, TISCO, RINL , JSW, JSPL**
Clause 10 B (i to iv)		**Deleted**
Clause 11		
Specification to be followed for execution of work.		**CPWD Specifications 2019 Volume I & II with up to date correction slips.**
Clause 12		
12.2 & 12.3	Deviation limit for value of any item of any individual trade beyond which sub clauses 12.1.2 (i) to (v) shall not apply and clauses 12.2.& 12.3 shall apply.	**100%**
Clause 16		
Competent authority for deciding reduced rates.		**Superintending Engineer (C), O/o PCE (C), BSNL UKD Civil Zone, Dehradun.**

Clause 36(i)

General guide lines for fixing requirement of technical staff and rate of recovery in case of non-compliance, for a work, shall be as per the following table

Sl. No.	Minimum Qualification of Technical Representative	Discipline	Designation (Principal/Technical Representative)	Minimum Experience	Number	Rate at which recovery shall be made from the contractor at the event of not fu filling provision of Clause 36(i)	
						Figures	Words
Not applicable							

Clause 37 (i)

	Levy / Taxes Payable by contractor. (in respect of GST)	The rates quoted shall be inclusive of all i.e. GST on raw material and its input tax credit, workers welfare cess, contribution towards EPF, Insurance, loading, unloading, transportation, taxes, levies and octroi. The GST towards work contract services as per GOI guidelines (presently considered as 18%) shall also to be included by the agency in his quote rates. Hence Income Tax/Construction workers welfare cess/ other taxes as applicable shall be recovered from contractor's bill & agency has to submit invoice showing break up of work done amount and GST. The GST shall be paid by the agency to the concerned department. **The rates quoted by the contractor shall be taken net and nothing extra shall be paid on any account i.e. royalty, cartage, GST, loading, unloading, octroi, other taxes, levies, insurance & workers welfare cess.**

Clause 42

i) Schedule / statement for determining theoretical quantities of cement on the basis of	**CPWD Delhi Schedule of Rates 2023 with up to date correction slips.**
ii) Variation permissible on theoretical quantities	
a) Cement for works with estimated costs put to tender	
i) Not more than Rs. 5 lakhs	3 % minus
ii) More than 5 lakhs	2 % minus
b) Steel reinforcement and structural steel sections for each diameter, section and category.	2 % minus

Star prices to be considered for escalation & recoveries

Sl. No.	Material	Star Price (Rate Per MT in Figures and Words)
1	For Cement (OPC)	**Rs.10,200/-(Rs. Ten Thousand Two Hundred) only per Ton i/c GST**
2(a)	For Mild steel	**NA**
2(b)	For Reinforcement Steel conforming to BIS 1786 (Fe 500D	**NA**

	Grade)	
2(c)	For Reinforcement Steel TMT bars **confirming to IS 1786:2008 from main producers as approved by the Ministry of steel, like SAIL TISCO, RINL,JSW, JSPL**	**Rs.77,000/-(Rs. Seventy Seven Thousand) only per Ton i/c GST**
2(d)	For Galvanized Steel	**NA**

The rate for recovery under clause 42 shall be same as the Star Price.

Executive Engineer (C),
BSNL Civil Division,
Haldwani

ADDITIONAL CONDITIONS

1.0 GENERAL

1.1 The "Contract" shall, in general, be governed by the BSNL General Conditions of Contract for Civil Works (A BSNL publication, available in downloadable manner from website **www.civil.bsnl.co.in**). However, all additions and modifications to the conditions as available in this tender document, consisting of following, shall also form part of the contract:

a) Notice Inviting Tender (i.e., BSNL W-6),

b) BSNL W-8 (i.e., Item Rate Tender & Contract for Works),

c) Schedules "A" to "F",

d) Additional Conditions,

e) Additional Specifications,

f) Special Conditions

g) Specifications for steel tower, and

h) Drawings and designs, if any,

i) Including agreement/ guarantee bonds on non-judicial stamp paper and acceptance thereof together with any correspondence leading thereto.

1.2 The quoted rates for various items in the tender shall be inclusive of all the additional/ special conditions and particular specifications; and for adherence to all these conditions and specifications, no extra payment shall be made to the contractor. Any infringement and/or breach of these specification and condition(s) etc. shall render the contractor liable to action(s) under various clauses of the contract and such action stipulated in conditions therein.

1.3 Wherever "CPWD Specification" is referred to in the tender documents; it shall mean "CPWD Specifications 2019 (Volume I & II)" with all up-to-date correction slips.

1.4 Wherever any reference to any Indian Standard Specifications (B.I.S.) occurs in the documents relating to this contract, the same shall be inclusive of all up-to-date amendments or revisions.

1.5 Wherever "DSR" is referred to in the tender documents, it shall mean "CPWD Delhi Schedule of Rates 2023" with all up to date correction slips as on the date of opening of tenders".

1.6 **RATE CLAUSE:** The rate for every item of work to be done under this contract shall be for all heights, depths, lengths and widths of the structure (except where specially mentioned in the item) and nothing extra will be paid on this account.

1.7 **In the event of no rate has been quoted for any item (s) then the rate for such item (s) will be considered as Zero and work will be required to be executed accordingly.** It will be presumed that the contractor has included the cost of this/ these item (s) in other item (s).

1.8 The agency shall intimate within 07 days of award of the contract, his contact telephone numbers (office / residence / mobile) & the name & contact telephone numbers (office / residence / mobile) of all site engineers, supervisors or his authorized representative (s).

1.9 The contractor shall comply with proper and legal orders and directions of the local or public authority or municipality and abide by their rules and regulations and pay all fees and charges which he may be liable and nothing extra shall be payable on this account. The work shall be carried out without infringing on any of the local Municipal Bye-Laws. **All local body approvals are the responsibility of the contractor.**

1.10 The contractors shall give a performance test of the entire installations as per standard specifications before the work is finally accepted and nothing extra whatsoever shall be payable to the contractor for the tests.

1.11 Some restrictions may be imposed by the security staff etc. on the working and/ or movement of labour, materials etc. and the contractor shall be bound to follow all such restrictions/ instructions and nothing extra shall be payable on this account.

1.12 **The contractor shall take sufficient safety measures to safeguard life & property** (structures, offices, roads, trees and plants including electrical, water supply, sanitary and telecommunication installations etc inside the compound) **of BSNL and of the owner of the property** where the work is going on, during execution of the work and shall be fully responsible for the damages on this account, if any.

1.13 The work may have to be executed in close proximity of private properties. The agency shall take adequate precautions for safety of such property and humans and schedule its work in liaison with the owner of the property

1.14 The contractor will have to extend full cooperation for contingent measures, which might be required to be taken due to eventuality.

1.15 The contractor will maintain discipline while working in the Compound. He or his employees will not indulge in any dispute with any Govt. employee/ public inside the compound and any default in this regard will be brought to the notice of the Engineer-in-Charge immediately.

1.16 Cleanliness of the compound will be maintained and any debris/ material falling in the compound in area in use of the staff/ public will be got cleared by the Agency regularly during the progress of work.

1.17 Any activity involving excessive noise, dust and pollution will be done by the contractor during holidays or and before office hours.

1.18 In the developed and in-use compounds, the contractor will not be allowed to erect labour huts and shall have to arrange at a location outside the compound at his own cost.

1.19 No payment shall be made to the contractor for any damage caused during the execution of work because of cause(s) not covered under Clause 43 of the Contract. Any damage done by the contractor to any existing work, existing building or structure of BSNL during the course of execution of work tendered for shall be made good by him at his own cost, and no claim on this account shall be entertained.

1.20 The contractor shall take all precautions to avoid all accidents by exhibiting necessary caution boards such as day and night boards, speed limit boards and flags, red lights and providing barriers etc. He shall be responsible for all damages and accidents caused due to negligence on his part. No hindrance shall be caused to traffic during the execution of work. Nothing extra shall be paid on this account.

1.21 The contractor will work in close liaison, during the works, with other contractors of water supply, sanitary, drainage arrangements, electrical installation and any other works and adjust his work plan accordingly.

1.22 The work should be carried out in such a manner that site shall be free of any construction material, excavated material or labour cabins etc. and is accessible to other agencies to carry out their works (i.e. erection of tower, electrical works etc.) simultaneously. Contractor must provide congenial atmosphere and extend full cooperation to other agencies for execution of their works.

1.23 The contractor shall leave such necessary holes, openings etc. for laying/ burying in the pipes, cables, conduits, clamps boxes and hooks for fan clamps etc. as may be required for the electric and sanitary works etc.

1.24 It may be clearly understood that all the sites may not have proper motorable approach roads and contractor will have to make his own arrangement for carrying the materials to the site of work. No payment / compensation will be payable on this account unless otherwise specified elsewhere.

1.25 The contractor shall make his own arrangement for obtaining electric / water connections, if required and make necessary payment directly to the Departments concerned. Vendor to make provision of appropriate rating DG set to support construction activity.

1.26 **Security Pass** Wherever necessary, security pass/ tokens for the construction workers shall be provided by the user as per prevalent rules and policies. Vendor must furnish required credentials for issuance of security pass. In case construction work has to be carried out beyond specified schedule, specific clearance for the same shall be obtained by the Vendor in advance.

1.27 Debris generated during the construction shall be cleared by the Vendor at his own expense. Contractor shall also remove from site materials as rejected by the User within reasonable time as specified by him.

1.28 The site of work may be changed, with mutual consent, within the same SSA/ BA for which nothing extra shall be payable except the approved contract rates.

1.29 **The job orders for more than one site at different stations or all stations may be issued simultaneously and work may be required to be carried out simultaneously. Therefore, the agency should have the requisite capability, finance, manpower, machinery etc. required to carry out more than one job orders or all simultaneously at different locations.**

1.30 All works executed shall be maintained in perfect condition by the contractor till the completion of entire work allotted to him. Where phased handing over of completed portion of the work is required by the Engineer-in-Charge, the provisions mentioned in these paras will apply to each phase.

1.31 The work shall be considered as complete only when it is successfully handed over to user. If any part or full has been rejected by the user for whatsoever reasons, the contractor shall have to make good or have to completely re-do the work in order to make it acceptable at his own cost and no claims shall be given on this account. All payments till such time shall be considered as advance payments and final payment shall be made only after successfully handing over of the work

1.32 The Executive Engineer may withdraw the works of the site where the contractor fails to show progress proportionally as per the agreement or suspended works for a period of more than Ten days. The Engineer-in-charge will be free to get the work completed at such sites in whatever manner deemed fit. A single notice followed by letter of decision in this regard from Engineer-in-charge to contractor will be conclusive & binding. The contractor will not be entitled for any compensation whatsoever in this regard. The Earnest Money, performance guarantee and security deposit will be considered as having equal share for all sites considered in the rate contract.

1.33 The bidder must note that the quality audit shall be carried out at various stages of the project and the contractor shall have to fully co-operate with the BSNL in this regard and extend necessary facilities for the same.

1.34 The completed work shall be inspected for approval by the **Acceptance Testing** unit of the BSNL. It shall be the responsibility of the contractor to offer the completed work for inspection and approval of the A/T in co-ordination with and as per the directions of the Engineer-in-charge and nothing extra shall be payable on this account. If the completed work is not found satisfactory as per the prescribed specifications, corrective measures as ordered by the Engineer-in-charge shall be carried out immediately by the contractor without any additional expenditure liability to the BSNL.

2.0 Storage and safety of materials

2.1 All the construction material shall be stored at site only at the specified location as decided by the Engineer-in-charge. In case the contractor fails to do the so, the Department shall be at the right and liberty to either seize the material or may shift at the cost of the contractor. The contractor shall have no claim on this account. The necessary expenditure shall be deducted from the running account bill of the contractor.

2.2 The Contractor shall maintain safe custody of materials brought to the site. The Contractor shall also employ necessary watch and ward establishment for the work and other purposes as required at his own cost.

2.3 Before commencement of the work, the contractor shall obtain written approval of the Engineer-in-Charge regarding the location of cement go-down, steel stacking and fabrication yard, site office etc and shall from time to time take instructions of the Engineer-in-Charge regarding collection and stacking of materials at the site. He shall have to make his own arrangement of space for storage of materials, if necessary.

3.0 PAYMENTS

3.1 First running account bill shall be paid only after

a) Signing of the Agreement / Contract by both the parties, and

b) Progress chart has been prepared as required under Clause 5 and approved by the competent authority.

3.2 The refund of SD shall be governed by Clause 17 of the standard contract from BSNL-8 as well as completion of works.

3.3 The rate indicated in the tender is net and is applicable to all locations irrespective of the hilly terrain, head load and quantity etc. The rate shall remain firm during the currency of the contract unless otherwise specified elsewhere.

4.0 OTHER TAXES AND ROYALTIES

4.1 The tenderers shall take into consideration the Drawings and Specifications and quote the rates accordingly. The quoted rates shall be comprehensive & complete including all charges. The rates offered should be inclusive of all taxes, levies Construction Workers Welfare Cess, Contributions towards EPF and GST. Insurance, loading, transportation etc. should be including on the quoted rates. The rate shall be firm & final. Nothing extra shall be paid over the quoted rates.

4.2 "Levy/ taxes payable by contractor" and "Conditions for reimbursement of levy/ taxes, if levied after receipt of tenders" are to be governed by Clause 37 & Clause 38 of General Conditions of Contract, as amended herein.

Amendment to Clause 37(i) & 38(i) of BSNL GCC

Clause	Existing Provisions	Modified Provisions
Clause 37 (i) of BSNL GCC	Sales Tax/VAT (except Service Tax), Building and other Construction Workers Welfare Cess or any other tax or Cess in respect of this contract shall be payable by the contractor and BSNL shall not entertain any claim whatsoever in this respect. However, in respect of Service Tax, same shall be paid by the contractor to the concerned department on demand and it will be reimbursed to him by the Engineer-in-Charge after satisfying that it has been actually and genuinely paid by the contractor.	**GST (as mentioned in Schedule F),** Building and other Construction Workers Welfare Cess or any other tax, levy or Cess in respect of input for or output by this contract shall be payable by the contractor and BSNL shall not entertain any claim whatsoever in this respect **except as provided under clause 38.** **If BSNL suffers any loss or claim due to non-compliance of any of the GST provisions by the contractor, the BSNL will take appropriate action against him, including recovery from the payments due to him.**

Clause 38 (i) of BSNL GCC	All tendered rates shall be inclusive of all taxes and levies (except Service Tax) payable under …….. …… the control of the contractor.	All tendered rates shall be inclusive of any tax, levy or cess applicable on last stipulated date of receipt of tender including extension if any. No adjustments i.e. increase or decrease shall be made for any variation in the rate of GST, Building and Other Construction Workers Welfare Cess or any tax, levy or cess applicable **oninputs**. However, effect of variation in rates of GST or Building and Other Construction Workers Welfare Cess or imposition or repeal of any other tax, levy or cess applicable **on output** of the works contract shall be adjusted on side, increase or decrease. Provided further that for Building and Other Construction Workers Welfare Cess or any tax (other than GST), levy or cess varied or imposed after the last date of receipt of tender including extension if any, any increase shall be reimbursed to the contractor **only if the contractor necessarily and properly pays such increased amount of taxes/levies/cess**. Provided further that such increase including GST shall **not** be made **in the extended period of contract** for which the contractor alone is responsible for delay as determined by authority for extension of time under Clause 5 in Schedule F.

4.3 **Income Tax and surcharges** over Income Tax etc. at the rates fixed by the Ministry of finance. Government of India shall be deducted from all the running and final bills of the contractor. Should there be any increase in rate of Income Tax and surcharge during execution of the contract, the same shall be payable by the contractor.

4.4 **Royalty** at the prevalent rates, wherever payable, shall have to be paid by the contractor direct to the Revenue authority of the State Government concerned for the materials like boulders, metal, shingle, sand, bajri or any other items collected by him for the execution of the work. “No Demand” certificate from the State Authority concerned shall be obtained before the final bill is paid for such royalty being paid directly, failing which recovery will be affected from him at the prevalent market rates.

4.5 The contractor shall pay **Octroi** wherever applicable. The Form ‘C’/ ‘D’, Octroi exemption certificates etc. will not be issued by BSNL for any materials required in the work. The contractor shall quote all-inclusive rates only. Nothing extra shall be paid on this account.

4.6 The worker welfare cess @1% shall be deducted from the bill of contractor.

4.7 As per the digitalization policy of Govt of India/ BSNL, all correspondences shall be done on Official E-mails of all concerned including transmission of award letter, letters &notes etc. related to the works.

ADDITIONAL SPECIFICATIONS

1.0 GENERAL

1.1 The Work shall, in general, conform to the **CPWD Specifications 2019 Vol 1 & 2, with up-to-date correction slips**.

1.1.1 Should there be any difference between the specifications mentioned above and the specifications given in the schedule of quantities, the later shall prevail.

1.1.2 If the specifications for any item are not available in the CPWD Specifications cited above, relevant BIS Specifications should be followed.

1.1.3 In case BIS Specifications are also not available, the decision of Engineer-in-Charge given in writing based on acceptable sound engineering practice and local usage shall be final and binding on the contractor.

1.2 The work will be carried out in accordance with the architectural drawings and structural drawings to be issued by the Engineer-in-Charge. The structural and architectural drawings shall have to be properly correlated before executing the work.

1.2.1 In case of any difference noticed between Architectural and Structural drawings, the contractor shall obtain final decision in writing from the Engineer-in-Charge.

1.2.2 In case of any discrepancy in the item given in the schedule of quantities appended with the tender and architectural drawings relating to the relevant item, former shall prevail unless otherwise given in writing by the Engineer-in-Charge

1.3 The following modifications to **CPWD Specifications** shall, however, apply.

2.0 PROCUREMENT OF RAW MATERIALS

2.1 **Stone Aggregate:** Stone aggregate used in the work shall be crushed or broken hard stone to be obtained from source/ quarry approved **by Engineer-in-charge** and shall conform to the relevant provisions in the CPWD specifications.

2.2 **Fine Sand/ Coarse Sand:** Coarse sand used in the work shall be obtained from source/ quarry approved **by Engineer-in-charge** and shall conform to the relevant provisions in the CPWD specifications.

2.3 **NOTE:** Where only one variety of sand is available, the sand will be sieved for use in finishing work to achieve the required particle size distribution as per CPWD Specifications or as directed by the Engineer-in-charge, in order to obtain smooth surface and nothing extra will be paid on this account.

2.4 **Sand for filling in Plinth:** The sand for filling in plinth under floor shall be obtained from approved source and shall conform to the relevant provisions in CPWD specifications.

2.5 **Water:** It shall conform to requirements laid down in IS: 456-2000 and CPWD Specifications.

2.6 **Bricks for Brick Work:** Bricks used in the work shall be well-burnt FPS bricks of uniform colour throughout the cross section to be obtained from approved kilns. In all other respect, it shall be local first class bricks, confirming to class designation 75 given in CPWD specifications.

2.7 All above materials like stone aggregates, coarse sand, fine sand, Bricks, Stone etc. confirming to the CPWD specifications to be brought from the sources approved by Engineer-in-Charge. In case, at any stage during execution of work, the material from the approved source being not available or otherwise, and, is required to be arranged from other sources conforming to relevant CPWD specifications and duly approved of Engineer-in-Charge, involving extra lead etc, nothing extra shall be paid on this account.

2.8 All materials brought to site by the Contractor must be offered for inspection and quality clearance by the Engineer or his representative before being used in the work and such approvals shall be recorded in an authorized register.

2.9 All paints/distemper/plastic paints to be used shall only be those manufactured by one of the firms mentioned in the “Preferred List of various items/ Products to be used in the work”.

(Samples of any material supplied by the Contractor may be got tested in any recognized laboratory, at the sole discretion of the User.)

3.0 PROCUREMENT OF READYMADE MATERIALS

3.1 Wherever it is desired to procure factory-made materials, such factory-made materials shall be procured from reputed and approved manufacturers or through their authorized dealers. The contractor shall obtain the approval from the Engineer-in-Charge of such firms prior to procurement of such factory-made materials. The Engineer-in-charge may, at any stage, inspect such factories/ manufacturing units. The contractor shall have no claim if the factory made materials brought to the site are rejected by the Engineer-in-charge in part or in full due to bad workmanship/ quality etc. even after the inspection of the manufacturing units.

3.2 The manufactured materials brought at site of work shall, in general, conform to the relevant specifications. The source for supply of the manufactured materials shall be approved by the Engineer-in-Charge. The contractor shall have no claim if the manufactured materials brought to the site are rejected by the Engineer-in-Charge in part or in full due to bad workmanship/ quality etc.

3.3 **The preference amongst the various alternative materials available** shall be as follows:

(a) The materials shall be as per the Brand specified to be used in the work.

(b) If the Brand specified material is not available then the material shall be ISI marked.

(c) If ISI marked item is not available then it should be from ISO certified Company.

(d) If the ISI marked or ISO certified items are not available then the best available items in the market to be procured.

3.4 **Equivalents for the various materials** and the materials of approved make shall be got approved from the Engineer-in-Charge of work in writing before using them on the work.

4.0 CEMENT AND STEEL (GENERAL)

4.1 **The contractor shall procure cement & steel as required in the work.** The quantities brought at site shall be entered in the respective material at site accounts and shall be treated as issued for maintenance of daily consumption.

4.2 The actual issue and consumption of steel and cement on the work shall be regulated and proper accounts maintained as provided in clause 10 of the contract. The theoretical consumption of steel shall be worked out as per procedure prescribed in clause 42 of the contract and shall be governed by conditions laid therein.

4.3 The daily account of the receipt/ issue of cement shall be maintained in a register in the prescribed proforma as given below & signed daily by the contractor or his authorised representative in token of its correctness:

Date Of Receipt	Particulars of Receipt		Particular of issue					Remarks			
	Quantity received invoice no & date	Progressive total	Date of issue	Quantity issued	Item of work for which issued	Quantity returned at the end of the day	Total issued	Daily Balance in hand.	Contractor's initials	JE's initials	AE/EE's periodical check
1	2	3	4	5	6	7	8	9	10	11	12

4.4 Steel and Cement brought to site and cement remaining unused after completion of work shall not be removed from site without the written permission of the Engineer-in-charge.

5.0 PROCUREMENT OF CEMENT

5.1 The contractor shall procure **43 grade** (conforming to IS:8112) Ordinary Portland Cement, as required in the work, from the reputed manufacturers of cement, having a production capacity of one million tonnes per annum or more, such as ACC, L&T, Vikram, Shri Cement and CCI and other manufacturers, as approved by the Ministry of Industry, Government of

India, and holding license to use ISI certification mark for their product, whose name shall be got approved from Engineer-in-charge. **Cement 53 grade shall not be used in the work.**

5.2 Supply of cement shall be taken in 50 kg bags, bearing manufacturer's name and ISI marking. Samples of cement arranged by the contractor shall be taken by the Engineer-in-charge and got tested in accordance with provisions of the relevant BIS codes. In case test results indicate that the cement arranged by the contractor does not conform to the relevant BIS codes, the same shall stand rejected and shall be removed from the site by the contractor at his own cost within a week's time of written order from the Engineer-in-charge to do so.

5.3 The total quantity of cement required shall be brought at site in one lot or as decided by the Engineer-in-charge.

5.4 The cement go-down of the capacity to store about 300 bags of cement or as decided by the Engineer-in-charge, shall be constructed by the contractor at site of work.

5.4.1 Cement go-down shall be in general as per the sketch shown in contract documents, having weather proof roof & walls and with a proper floor consisting of 2 layers of dry bricks laid on the well consolidated earth at a level at least one foot above the ground level. The cement bags shall be stacked about 200mm (clear) above the dry brick flooring using suitable wooden planks / battens. The stacks shall be in rows of two bags deep and 10 bags high with a minimum of 2 feet clear space all around. The bags should be placed horizontally continuous in each line. Nothing extra shall be paid to the contractor on this ground.

5.4.2 The size of cement go-down indicated in the contract form is only for guidance. The actual size of the go-down shall be constructed by the contractor at his own cost, as per the requirement of work.

5.4.3 Double lock provision shall be made to the door of cement go-down. The keys of one lock shall remain with the Engineer-in-charge or his authorized representative and the keys of other lock shall remain with the contractor. The contractor shall facilitate the inspection of the cement go-down by the Engineer-in-charge at any time.

5.4.4 The contractor shall be fully responsible for the safe custody of the material even if the material is under double lock system.

6.0 PROCUREMENT OF STEEL

6.1 The contractor shall procure steel reinforcement bars conforming to relevant BIS codes from main producers as approved by the Ministry of steel or as specified in schedule –F.

6.2 The contractor shall have to obtain and furnish test certificates to the Engineer-in-charge in respect of all supplies of steel brought by him to the site of work. Samples shall also be taken and got tested by the Engineer-in-charge as per the provisions in this regard in the relevant BIS codes. In case the test results indicate that the steel arranged by the contractor does not conform to BIS codes, the same shall stand rejected and shall be removed from the site of work within a week's time of written order from the Engineer-in-charge to do so.

6.3 The steel reinforcement shall be brought to the site in quantity of lots as approved by the Engineer-in-charge.

6.4 The steel reinforcement shall be stored by the contractor at site of work in such a way as to prevent distortion and corrosion and nothing extra shall be paid on this account. Bars of different sizes (diameters) and lengths shall be stored separately to facilitate easy counting and checking.

6.5 For steel procured from main producers, for checking nominal mass, tensile strength, bend test, etc. specimen of sufficient length shall be cut from each diameter of the bar at random at frequency not less than that specified below. In case of works costing more that2 Crores and when the steel is procured from other than main producers, additional tests such as, retest, re-bend test, elongation test, proof stress may also be conducted

Size of bar	For consignment below 100 tonnes	For consignment over 100 tonnes
Under 10 mm dia	One sample for each 25 tonnes or part thereof	One sample for each 40 tonnes or part thereof
10 mm to 16 mm dia	One sample for each 35 tonnes or part thereof	One sample for each 45 tonnes or part thereof
Over 16 mm dia	One sample for each 45 tonnes or part thereof	One sample for each 50 tonnes or part thereof

6.6 Coefficient of weight i.e. the weight per unit length of the Steel procured by the contractor shall be ascertained at site before using it and certified by the Engineer-in-charge. In case weight per unit length is beyond the rolling margin as laid down in the BIS: 1786, the steel will be rejected and shall be removed as per para 1 above. In case weight per unit length is more than the standard coefficient of weight for the diameter, but is within the rolling margin, then the payment shall be made as per the standard weight per unit length, and, where the weight per unit length is lesser than the standard coefficient of weight for the diameter, but is within the rolling margin, the payment shall be restricted with respect to the actual weight per unit length of the diameter.

6.7 The standard sectional weights referred to in standard table under para 5.3.4 of the CPWD Specifications 2019 are to be considered for conversion of length of various sizes of Steel Reinforcement bars into weight and are reproduced below for ready reference.

Size (Diameter in mm)	Weight (Kg./M.)	Size (Diameter in mm)	Weight (Kg./M.)
6	0.222	20	2.470
8	0.395	25	3.850
10	0.617	28	4.830
12	0.888	32	6.310
16	1.580	36	7.990

7.0 TESTING OF MATERIALS & RELATED ASPECTS

7.1 **WORK SAMPLES:** For items where so desired, samples shall be prepared before starting the particular items of work for prior approval of the Engineer-in-Charge and nothing extra shall be payable on this account.

7.2 **Materials brought at site of work shall not be used in the work before getting satisfactory Mandatory test results.** For details, relevant provisions in the CPWD specification shall be referred to.

7.3 If the testing specifications for any material are not available in the CPWD Specifications cited above, relevant BIS Specifications should be followed.

7.4 The contractor shall procure and submit all the materials/ samples in advance, so that there is sufficient time for testing of the same before use in work.

7.5 **Samples of various materials required for testing shall be provided free of charge by the contractor. However the cost of the tests shall be paid by the contractor which shall be reimbursed by BSNL, only if the test reports are satisfactory. The test shall be got done only from lab approved by the Engineer-In-Charge.**

7.6 All other expenditures incurred for testing such as packing, sealing, transportation, loading, unloading etc shall be borne by the contractor himself.

7.7 **Part rate payment shall be allowed in the running account bills only if the materials conforming to the CPWD specifications for works as mentioned in the work are tested and test results are found to be satisfactory by the Engineer-in-Charge.**

7.8 The Engineer-in-Charge of work shall check the test results and satisfy himself before allowing any payment in the running/final bill.

7.9 No claims of any kind whatsoever including the claim of extension of time shall be entertained due to incorporation of above requirements for testing of materials.

7.10 **The Make/Brand once approved shall not be changed during the currency of the agreement without prior approval of Engineer-in-charge.**

7.11 **CC Cube Test:** With a view to avoid controversy about quality of cement concrete as revealed in the test result of 7 days cubes falling short of the prescribed standard by over 10% to 20% and pending testing of balance 3 cubes for 28 days as final confirmatory acceptance test, crushed samples of cement concrete from the failed 7 days cubes should be preserved in a sealed bag.

8.0 General MEASUREMENT OF WORK:

8.1 **The work shall be executed and measured as per Metric Dimensions** given in the schedule of quantities, drawings etc. (FPS units wherever indicated are for guidance only).

9.0 EARTH WORK

9.1 During excavation and trenching work etc. the contractors shall ensure compliance to the guidelines in such matters laid down by the local body/bodies to ensure that there is minimum hazard to the operating personnel's and users, minimum inconvenience to the users, minimized damage to the underground plant/services of other utilities in a coordinated way, in the interest of public convenience and overall safety.

9.2 Any trenching and digging for laying sewer lines/water lines/cables etc. shall be commenced by the contractor only when all men, machinery and materials have been arranged and closing of the trench (s) thereafter shall be ensured within the least possible time.

9.3 **Surplus excavated earth which is beyond the requirement shall have to be disposed off by the contractor at his own cost** beyond the municipal limits or at places identified by local bodies or as directed by Engineer-in-charge,after obtaining written permission of the Engineer-in-charge and no payment will be made by the BSNL for disposal of this surplus excavated earth.

9.4 The excavated earth (or building materials) shall not be stacked on areas where other buildings, road, services or compound wall or any other structure are to be constructed.

9.5 **DEWATERING CLAUSE:** The contractor shall, **at his own expense and without any extra charge, make provision for all shoring, pumping, dredging or bailing out water, if necessary.** The foundation trenches shall be kept free from water, while all the works below ground level are in progress, without any extra payment. The water may be coming from any source such as rains, floods, subsoil water or due to any other cause whatsoever etc.

10.0 PLAIN AND REINFORCED CEMENT CONCRETE WORK

10.1 **Non-destructive Testing for Concrete/R.C.C Work:** - The Engineer-in-Charge shall, at his discretion, get the non-destructive testing (Such as Ultrasonic Pulse Velocity Test etc.) done and the Contractor shall make all necessary arrangements for getting such tests done and make good the same after the test, for which nothing extra shall be paid. The results of such tests shall be binding on the Contractor. In case of nonconformity of the test to the standards, the contractor shall be liable to redo the concrete work at his cost including the cost of test, subject however, to the acceptability of the work as laid down in the mandatory test defined in the relevant CPWD specifications.

10.2 **Cement slurry, if any, added over base surface (or) for continuation of concreting for better bond is deemed to have been in built in the items** (Unless otherwise explicitly stated) and nothing extra shall be payable (or) extra cement considered in consumption on this account.

10.3 **Proper Grooves shall be provided in plaster along junctions of RCC Work and Brick/Stone work** as per directions of the Engineer-in-charge and **nothing extra will be paid on this account.**

10.4 In the item of RCC walls, railings and roofs etc. nothing extra shall be paid for making designs as per pattern given by Architects or for thickness of sections.

10.5 The rate of item for reinforcement in R.C.C. work includes all operations including straightening, cutting, bending, binding with annealed steel wire and placing in position at all the floors with all leads and lifts complete.

11.0 Centering and Shuttering For R.C.C. Work

11.1 The concrete surface shall be free from honeycombing, offsets, superfluous mortar, cement slurry and foreign matter. The formwork shall be assembled in such a way as to facilitate removal of their parts in proper sequence without any damage to the exposed cement concrete surfaces and corners etc.

11.2 **The contractor shall keep skilled staff for special care and supervision to check the formwork and concreting** so that every member is made true to its size, shape, level and alignment so that it does not result in any deformation, snug, bulges etc. The contractor shall also take suitable precautionary measure to prevent breaking and chipping of corners and edges of completed work until the building is handed over.

11.3 **The size of shuttering plates for slabs shall not be less than 0.6mx0.9m in general.** However,

contractor has to provide tape or wooden fillets or rubber gaskets to seal the joint properly to get smooth surface.

11.4 Further, shuttering shall be of such quality that there are no undulations and surfaces will be fairly even and no extra thick ceiling plaster shall be permitted to make the surface even. Any honeycombed or poorly formed concrete shall be repaired with polymer concrete of any suitable design by the Contractor at his own cost, in accordance with the specifications laid down in hand book of Repairs and Rehabilitation of RCC Buildings by CPWD.

11.5 **Steel centring & shuttering, scaffolding and props shall be used for all the items of RCC.** All propping and centring shall be either of steel tubes with extension pieces or built up sections of rolled steel. Shuttering used for concreting shall be sufficiently stiffened and of good quality mild steel plates free from dents, bends or warping and rusting. For shuttering of beam bottom, staircase and fins and for other places where use of steel shuttering is not found to be feasible, waterproof shuttering ply shall be used with prior approval of the engineer-in-charge.

11.6 **All scaffolding, centring and shuttering shall be with properly designed system** which shall be got approved from Engineer-in-Charge and centring and shuttering required for RCC work will be brought to site by the contractor well in advance so that the progress of the upper floors is not hampered due to non-availability of the same. Nothing extra shall be paid for this.

11.7 In respect of **projected balconies, projected slabs at roof level and projected verandah,** payment for the RCC work shall be made under the item of RCC slabs. The payment for centring and shuttering of such item shall similarly be paid under the item of centring and shuttering of RCC slab., all the exposed edge shall however, be finished as per specification and nothing extra shall be paid for this.

12.0 STONE WORK

12.1 Stone used for stone masonry work shall be hard granite/ basalt/ quartz stone/sand stone to be obtained from quarries approved by Engineer-In-Charge and shall conform to the relevant provision in the CPWD specifications.

13.0 WOOD WORK

13.1 Timber required for manufacture of chowkhats and shutters for doors, windows, ventilators, and partitions etc. in the work shall be kiln seasoned and preservative treated. The Timber shall be kiln seasoned before applying preservative treatment. The rate quoted for various items shall be inclusive of kiln seasoning and preservative treatment of wood. The wood used in the work shall conform to the provisions in the CPWD Specifications for works.

14.0 FACTORY MADE SHUTTERS etc.

14.1 The shutters for doors, windows & ventilators, and, chowkhats etc. shall be factory made and obtained from suppliers approved by the Engineer-in-charge.

15.0 STEEL WORK

15.1 All steel doors, steel windows, steel ventilators, wire gauge, steel glazing, steel grill shall be according to the Architect's detailed drawings and factory made and obtained from approved suppliers.

15.2 In the case of composite steel windows the rates shall include the cost of coupling mullion and transom etc. Where windows with inside openable shutters are fixed along-with windows with shutters openable outside, such inside openable windows shall be fitted with suitable friction hinges and openable outside with box type hinges, lever handles or otherwise as approved by the Engineer-in-Charge of the work. For such windows, cement concrete blocks of size 15cmx 10cmx 10cm shall be provided. Nothing extra shall be paid on this account.

15.3 In the case of steel windows and doors, steel glazing, wire gauge steel ventilators, rolling shutters, grills etc. an approved quality-priming coat of zinc chromate shall be applied over and above shop coat of primer. Nothing extra shall be payable for providing shop-coat primer.

16.0 SANITARY AND WATER SUPPLY INSTALLATIONS

16.1 The contractor shall engage licensed plumber for sanitary, water supply, drainage work and also get all the materials and system (including the materials supplied if any, by the department) tested by the Municipal Authority, whenever required, at his own cost including testing fees, transport etc. according to Municipal by Laws. The contractor shall produce necessary certificate from the Municipal Authorities after completion of work. Nothing extra will be paid on this account.

16.2 The water supply sanitary installation and drainage work shall be carried out in a manner complying in all respects with the requirement of relevant by-laws of the local municipal authority of the place at no

extra cost of the department.

16.3 The Contractor shall give a guarantee after completion in respect of water supply and sanitary installation, to the effect that the work shall remain structurally stable and shall guarantee against faulty workmanship, finishing, manufacturing defects of materials and leakages etc. The Contractor shall furnish a Guarantee Bond, as per prescribed format. The Guarantee Period shall be for 10(Ten) years.

17.0 APPROVAL OF SAMPLE WORK OF REPETITIVE/ TYPICAL NATURE

17.1 Approval of sample work of repetitive/ typical nature prior to general execution of work shall be as enumerated hereafter.

17.2 Samples of typical portion of the works of repetitive nature such as typical room, toilet room, or any other work shall be prepared by the contractor under the directions and to the satisfaction of Engineer-in-Charge and got approved from him in writing before the commencement of these items for the entire work.

17.3 The work shall be so arranged to be carried out that the requirement for preparation of samples are observed and fulfilled without any detriment to the general progress of work. In other words, this will not be allowed to have any effect on the general progress of work or on any of the terms and conditions of the contract. No claims of any kind whatsoever including the claim of extension of time will be entertained due to the incorporation of this requirement.

18.0 WATER PROOFING:

18.1 For the treatment of Roof Surfaces wherever done, relevant CPWD/ particular specifications shall be applicable.

18.2 The Contractor shall associate himself with the specialized firm, to be approved by the Engineer-in-charge, for execution of water proofing treatment. The contractor shall furnish a Guarantee Bond, as per prescribed format, from the specialized firm and duly counter-signed by the contractor as a token of overall responsibility. The Guarantee Period shall be for 10(Ten) years.

18.3 Ten percent of the cost of items of water proofing treatment for sunken floors and on roofs would be retained as guarantee to watch the performance of the work done. However half of the amount withheld would be released after (5) five years, if the performance of the work done is satisfactory. If any defect is noticed during the guarantee period, it should be rectified by the contractor within seven days, and if' not attend to, the same will be got done from another agency at the risk and cost of the contractor. However this security deposit can be released in full, if bank guarantee of equivalent amount for 10(ten) years after completion of maintenance period is produced and deposited with the BSNL.

Executive Engineer (Civil)
BSNL Civil Division
Haldwani

SPECIAL CONDITIONS FOR THE WORK

1.0. GENERAL

The contractor shall take sufficient safety measures to safeguard life and property of BSNL (structures, offices, roads, trees and plants including electrical, water supply, sanitary and telecommunication installations etc) inside the compound during execution of the work and shall be fully responsible for the damages on this account, if any.

1.1 The contractor will quote his rate inclusive of all taxes, levies and GST as per GOI Guidelines.

1.2 The deduction at source of such taxes as per rule shall be made while releasing payment of the running/final bills at the rate as applicable. The department shall issue a certificate of the rate and amount of deductions.

1.3 All local body approvals are the responsibility of the contractor.

1.4 The agency shall intimate within 07 days of award of the contract, his contact telephone numbers (office / residence / mobile) & the name & contact telephone numbers (office / residence / mobile) of all site engineers, supervisors or his authorized representative (s).

1.5 No payment shall be made to the contractor for any damage caused during the execution of work because of cause(s) not covered under Clause 43 of the Contract (Like damage caused by rain, lightning, wind, storm, snow fall, floods, earth quake or any other natural cause/calamity etc). The damage to work will be made good by the contractor at his own cost, and no claim on this account shall be entertained.

1.6 **The contractor shall comply with proper and legal orders and directions of the local or public authority or municipality and abide by their rules and regulations** and pay all fees and charges which he may be liable and nothing extra shall be payable on this account. The work shall be carried out without infringing on any of the local Municipal Bye-Laws.

1.7 Before commencement of the work, the contractor shall obtain written approval of the Engineer-in-charge regarding the location of cement Godown, steel stacking and fabrication yard, site office etc and shall from time to time take instructions of the Engineer-in-charge regarding collection and stacking of materials at the site. He shall have to make his own arrangement of space for storage of materials, if necessary

1.8 The contractor shall take all precautions to avoid all accidents by exhibiting necessary caution boards such as day and night boards, speed limit boards and flags, red lights and providing barriers etc. He shall be responsible for all damages and accidents caused due to negligence on his part. No hindrance shall be caused to traffic during the execution of work. Nothing extra shall be paid on this account

1.9 All the construction material shall be stored at site only at the specified location as decided by the Engineer-in-charge. In case the contractor fails to do the so, the Department shall be at the right and liberty to either seize the material or may shift at the cost of the contractor. The contractor shall have no claim on this account. The necessary expenditure shall be deducted from the running account bill of the contractor.

1.10 The work shall be considered as complete only when it is successfully handed over to user. If any part or full has been rejected by the user for whatsoever reasons, the contractor shall

have to make good or have to completely re-do the work in order to make it acceptable at his own cost and no claims shall be given on this account. All payments till such time shall be considered as advance payments and final payment shall be made only after successfully handing over of the work

1.11 The contractors shall give a performance test of the entire installations as per standard specifications before the work is finally accepted and nothing extra what so ever shall be payable to the contractor for the tests.

1.12 Any damage done by the contractor to any existing work, existing building or structure of BSNL during the course of execution of work tendered for shall be made good by him at his own cost.

1.13 The contractor will work in close liaison, during the works, with other contractors of tower excretion, electrical installation and any other works and adjust his work plan accordingly.

1.14 The contractor shall leave such necessary holes, openings etc. for laying/ burying in the pipes, cables, conduits, clamps boxes and hooks for fan clamps etc. as may be required for the electric and sanitary works etc.

1.15 The contractor will have to extend full cooperation for contingent measures, which might be required to be taken due to eventuality.

1.16 The contractor will maintain discipline while working in the Compound. He or his employees will not indulge in any dispute with any Govt. employee/public inside the compound and any default in this regard will be brought to the notice of the Engineer-in-Charge immediately.

1.17 Cleanliness of the compound will be maintained and any debris/ material falling in the compound in area in use of the staff/ public will be got cleared by the Agency regularly during the progress of work.

1.18 Any activity involving excessive noise, dust and pollution will be done by the contractor during holidays or and before office hours.

1.19 In the developed and in-use compounds, the contractor will not be allowed to erect labour huts and shall have to arrange at a location outside the compound at his own cost.

1.20 All works executed shall be maintained in perfect condition by the contractor till the completion of entire work allotted to him. Where phased handing over of completed portion of the work is required by the Engineer-in-Charge, the provisions mentioned in the above paras will apply to each phase.

1.21 RATE CLAUSE: The rate for every item of work to be done under this contract shall be for all heights, depths, lengths and widths of the structure (except where specially mentioned in the item) and nothing extra will be paid on this account.

1.22 The Executive Engineer may withdraw the works of the site where the contractor fails to show progress proportionally as per the agreement or suspended works for a period of more than Ten days. The Engineer-in-charge will be free to get the work completed at such sites in whatever manner deemed fit . A single notice followed by letter of decision in this regard from Engineer-in-charge to contractor will be conclusive & binding. The contractor will not be entitled for any compensation what so ever in this regard. The Earnest Money Declaration, performance guarantee and security deposit will be considered as having equal share for all sites considered in the rate contract.

1.23 It may be clearly understood that all the sites may not have proper motor able approach roads and contractor will have to make his own arrangement for carrying the materials to the

site of work. No payment / compensation will be payable on this account unless otherwise specified elsewhere.

1.24 The work should be carried out in such a manner that site shall be free of any construction material, excavated materialor labour cabins etc and is accessible to other agencies to carry out their works (i.e. erection of tower, electrical worksetc) simultaneously. Contractor must provide congenial atmosphere and extend full cooperation to other agencies forexecution of their works.

1.25 DEWATERING CLAUSE: The contractor shall at his own expense and without any extra charge ,make provision for allshoring, pumping, dredging or bailing out water ,if necessary. The foundation trenches shall be kept free from water, whileall the works below ground level are in progress without any extra payment. The water may be coming from any sourcesuch as rains, floods, subsoil water or due to any other cause whatsoever etc.

1.26 The job orders for more than one site at different stations or all stations may be issued simultaneously and work may berequired to be carried out simultaneously. Therefore, the agency should have the requisite capability, finance, manpower,machinery etc. required to carry out more than one job orders or all simultaneously at different locations.

1.27 The work is to be executed in close proximity of private properties. The agency shall take adequate precautions forsafety of such property and humans and schedule its work in liaison with the owner of the property.

1.28 The site of work may be changed, with mutual consent, with in the same SSA for which nothing extra shall be payableexcept the approved contract rates.

1.29 The completed work shall be inspected for approval by the Acceptance testing unit of the BSNL. It shall be theresponsibility of the contractor to offer the completed work for inspection and approval of the A/T in co-ordination withand as per the directions of the Engineer-in-charge and nothing extra shall be payable on this account. If the completedwork is not found satisfactory as per the prescribed specifications, corrective measures as ordered by the Engineer-inchargeshall be carried out immediately by the contractor without any additional expenditure liability to the BSNL.

1.30 Before commencement of the work, the contractor shall obtain written approval of the Engineer-in-charge regarding the location of cement Godown, steel stacking and fabrication yard, site office etc and shall from time to time take instructions of the Engineer-in-charge regarding collection and stacking of materials at the site. He shall have to make his own arrangement of space for storage of materials, if necessary.

1.31 All emergent nature of complaints shall be attended to within 48 hours of the registration of complaints on all days or as directed by Engineer-in-Charge or his authorized representatives keeping in view the urgency failing which penalty @ Rs.200/ - per case/per day shall be imposed. Routine nature complaints may be attended within 72 hours.

1.32 In case of failure on part of agency to attend the complaints within reasonable time as instructed by the Engineer-in-charge or his authorized representatives, the same shall be got executed at risk & cost of agency apart from action under note 1.31 as above

2.0 WATER PROOFING:

For the treatment of Roof Surfaces wherever done, relevant CPWD/ particular specifications shall be applicable.

2.1 The Contractor shall associate himself with the specialized firm, for execution of water proofing treatment and laying of membrane shall also be carried through the authorized applicator of the manufacturer of the membrane, both i.e. the membrane

and the authorized applicator are to get approved by the Engineer-in-charge, prior to start of the work. The contractor shall furnish a Guarantee Bond, as per prescribed format, from the specialized firm and duly counter-signed by the contractor as a token of overall responsibility. The Guarantee Period shall be for 10(Ten) years.

2.2 Ten percent of the cost of items of water proofing treatment for sunken floors and on roofs would be retained as guarantee to watch the performance of the work done. However half of the amount withheld would be released after (5) five years, if the performance of the work done is satisfactory. If any defect is noticed during the guarantee period, it should be rectified by the contractor within seven days, and if' not attend to, the same will be got done from another agency at the risk and cost ofthe contractor. However this security deposit can be released in full, if bank guarantee of equivalent amount for 10(ten) years after completion of maintenance period is produced and deposited with the BSNL.

3.0 Storage and safety of materials

3.1 The Contractor shall maintain safe custody of materials brought to the site. The Contractor shall also employ necessary watch and ward establishment for the work and other purposes as required at his own cost.

3.2 Before commencement of the work, the contractor shall obtain written approval of the Engineer-in-Charge regarding the location of cement go-down, steel stacking and fabrication yard, site office etc and shall from time to time take instructions of the Engineer-in-Charge regarding collection and stacking of materials at the site. He shall have to make his own arrangement of space for storage of materials, if necessary.

4.0 PAYMENTS

4.1 The refund of SD shall be governed by Clause 17 of the standard contract from BSNL-8 as well as completion of works.

4.2 The rate indicated in the tender is net and is applicable to all locations irrespective of the hilly terrain, head load andquantity etc. The rate shall remain firm during the currency of the contract unless otherwise specified elsewhere.

5.0 OTHER TAXES AND ROYALTIES

5.1. The tenderers shall take into consideration the Drawings and Specifications and quote the rates accordingly. The quoted rates shall be comprehensive & complete including all charges. The rates offered should be inclusive of all taxes, levies and GST. Insurance, loading, transportation etc. should be including on the quoted rates. The rate shall be firm & final. Nothing extra shall be paid over the quoted rates.

Executive Engineer (Civil)
BSNL Civil Division
Haldwani

GUARANTEE BOND TO BE EXECUTED BY THE CONTRACTOR FOR WATER PROOFING TREATMENT FOR BASEMENT/TERRACE/TOILETS

The agreement made this_____day of _____two thousand and _____between_____S/o_____(hereinafter called the GUARANTOR of the one part) and the BHARAT SANCHAR NIGAM LIMITED (hereinafter called the BSNL of the other part).

WHEREAS this agreement is supplementary to a contract. (Herein after called the Contract) dated_____and made between the GUARANTOR OF THE ONE PART AND the BSNL of the other part, whereby the contractor interalia, undertook to render the structures in the said contractor of the work in the said contract recited completely water and leak proof.

THE GUARANTOR hereby guarantee that the water proofing treatment given by him will render the structures completely leak proof and the minimum life of such water proofing treatment shall be ten years to be reckoned from the date after the expiry of maintenance period prescribed in the contract.Provided that the guarantor will not be responsible for leakage caused by earthquake or structural defects. The decision of the Engineer in charge with regard to cause of leakage shall be final.During the period of guarantee the guarantor shall make good all defects and in case of any defects being found render the structure water proof to the satisfaction of the Engineer in charge at his cost and shall commence the work for such rectification within seven days from the date of issue of notice from the Engineer in charge calling upon him to rectify the defects, failing which the work shall be got done by the BSNL through some other contractor at the guarantor's cost and risk. The decision of the Engineer in charge as to the cost payable by the Guarantor shall be final and binding.

That if the guarantor fails to execute the water proofing, or commits breach there-under then the guarantor will indemnify the Principal and his successor against all loss, damage, cost of expenses or otherwise which may be incurred by him by reason of any of any default on the part of the GUARANTOR in performance and observance of this supplementary agreement.

As to the amount of loss and/or cost incurred by the BSNL on the decision of the Engineer in charge will be final and binding on the parties.

IN WITNESS WHEREOF those presents have been executed by the obligator _____and_____by for and on behalf of the BHARAT SANCHAR NIGAM LIMITED on the day, month and year first above written.

Signed sealed and delivered by OBLIGATOR in presence of:

1._____

2._____

SIGNED FOR AND ON BEHALF OF THE BHARAT SANCHAR NIGAM LIMITED BY

_____

_

In presence of:

1._____

2._____

PREFERRED LIST OF VARIOUS ITEMS/ PRODUCTS TO BE USED FOR THE WORK

Name of work: ***Day to day maintenance works in TE compound at Haldwani, Nainital for four months.***

SN	Name of Materials	Preferred Makes
1	Cement conforming to IS 8112:1989 IS 1489 (Part-I)	Ordinary Portland Cement 43 grade (Conforming to IS: 8112)/from reputed manufactures of cement such as A.C.C., Jay Pee Cement, Reliance, Ultratech, Shri Cement, GujratAmbuja Cement and Cement Corporation of India etc.
2	Sand (Coarse / Fine)	River sand (Source to be approved by Engineer-in-Charge.)
3	Stone Aggregate	Source to be approved by Engineer-in-Charge.
4	Synthetic Enamel paint/ Primers	First Quality of Asian, Louis Berger, ICI Dulux, Nerolac
5	Water Proofing material	Asian, Cico, Pidilite, Accoproof&Impermo
6	3 mm thick APP Sheet	Asian, Bitumat, Apex & STP Ltd., Torch Tarmembarane& Bitumen Product Pvt. Ltd.
1	Ordinary Portland cement/ Pozzolona Cement (Grey) - 43 Grade	ACC, Ultratech, Gujarat Ambuja, Vikram, Birla, JKCement, Shree.
2	Reinforcement Steel conforming to BIS 1786 (FE 500D Grade)	As per Schedule F Clause 10
3	White Cement & Wall Putty	Birla White / J. K. White
4	Mica/Laminates	Green, Century, Merino , Star, Virgo
6	PVC Pipe & Fittings	Supreme, Finolex& Prince.
7	Acrylic Distemper / Plastic Paint / OBD/ Exterior Paints	NEROLAC, ASIAN PAINTS , BERGER ,DULUX ICI , SHALIMAR
9	Steel /wood Primer/ Cement Primer	DULUXICI, ASIAN, NEROLAC , BERGER, SHALIMAR
10	Water Proofing Cement Paint	Acrocem, Arrocem , Acro , Anex
11	Stainless Steel Sink (Out of Salem Steel only)	DIAMOND, NIRALI, Neelkanth&Jayna
12	Plastic Seat Cover of W.C. (ISI Mark only)	Commander, Hindware, Admiral, Parryware&Cera
13	CP Fittings / Mixer / Pillar taps/ Water Taps / CP Accessories	ESS, JaquarEssco , Hindware, Somany , Cera, Parryware, Seiko, Bens
14	Centrifugally Cast (Spun) Iron Pipes and fittings	ISI Mark only
15	G.I. Pipes	Jindal (Hissar) & TATA
16	G.I. Fittings	Unik& UU or ISI Mark only
17	Aluminium Sections	Hindalco, Jindal, Indalco
18	Ceramic wall & floor Tiles	CERA, Johnson, Kajaria, Somany, Orient Bell
19	Vitrified Tiles	CERA, Johnson, Orient , Kajaria, Somany , Orient Bell
20	Particle Board/block board /plywood /laminated board / Flush Door	Greenply, Century, Merino ,Duro, Archid , Samrat
21	POLYETHYLENE WATER STORAGE TANK	SINTEX, VECTUS, FRONTIER, KAVARI,
22	FALSE CEILING TILES	Armstrong / Hunter Doglus / India Gypsum
23	PVC pipes and fittings	Supreme , Astral , Finolex
24	W.C., EWC, Wash Basin, Urinal & Urinal Partition, Plates and other vitreous china sanitaryware	Hindware, Parryware , Cera,Somany & Jaguar

NOTE:

1. For any other make, prior approval of Engineer-in charge is required before execution in work. All mandatory tests and other tests shall be made as per the departmental guidelines applicable and as required by Engineer-in-charge.
2. The contractor at his own cost shall ensure before tendering samples for approval of material/article that the material/article of above mentioned Manufacturers/Agencies/brand/make shall fully comply with the item nomenclature, drawings, Agreement specifications, CPWD Specifications 2009, Test results etc. Any deviation shall be brought to the notice of the Engineer-in-charge. Failure on all or any of the aforementioned accounts, the sample shall be rejected. The decision of Engineer-in-charge in this regard shall be final and binding on the contractor.

Executive Engineer (Civil)

CERTIFICATE

I/we hereby undertake that I/We/My authorized representative have received the copy of the stated list (along with the tender document) of brand names of various items to be used for the above work and I/We shall quote my rates of various items of schedule accordingly.

I hereby also certify that I shall use only the above referred brands in the work and in case any other brand is used then I shall not claim for the payment of that item.

Signature of Contractor or his authorized representative with seal

Schedule of Quantity

(For view purpose only)

Name of work:-" Day to day maintenance works in TE compound at Haldwani, Nainital for four months."

Estimated Cost: Rs. 2,49,631/- **Earnest Money:** Rs. 4,993/- **Time:** 04(Four) months

I.No.	Description of Item	Quantity	Rate (Rs)	Unit	Amount(Rs)
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
a	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.50		One Cubic Metre	
b	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.50		One Cubic Metre	
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge..				
a	In cement mortar	1.00		One Cubic Metre	
3	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead:				
a	Of area 3 sq. metres and below	4.00		Each	
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5.00		One Square Metre	
5	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	15.00		One Square Metre	
6	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	4.00		One Cubic Metre	
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
a	1:2:4 (1 Cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources).	0.50		One Cubic Metre	
b	1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	1.00		One Cubic Metre	

8	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
a	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.50		One Cubic Metre	
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
a	Thermo-Mechanically Treated bars of grade Fe-500D or more.	28.00		One Kilogram	
10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
a	Cement mortar 1:6 (1 cement : 6 coarse sand)	0.50		One Cubic Metre	
11	Deduct for not providing hinges in doors, windows or clerestory window shutters with :				
i	ISI marked Stainless steel butt hinges with stainless steel screws : For 2nd class teak wood and other class of wood shutters	4.00		One Square Metre	
i	ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. For 2nd class teak wood and other class of wood shutters	4.00		One Square Metre	
12	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
a	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	4.00		One Square Metre	
13	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws :				
i	30 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size - Kiln seasoned selected class of sheesham wood	4.00		One Square Metre	
14	Providing and fixing nickel plated M.S. pipe curtain rods with nickel plated brackets :				
a	20 mm dia (heavy type)	10.00		One Metre	
15	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	4.00		Each	

16	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :				
a	250x16 mm	4.00		Each	
17	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :				
a	250x10 mm	4.00		Each	
18	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :				
a	125 mm	4.00		Each	
19	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.				
a	Twin rubber stopper	8.00		Each	
20	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	10.00		One Kilogram	
21	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
a	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	20.00		One Kilogram	
22	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kgper sqm including pointing the joints with white cement mixed with pigment of matching shade complete.	12.00		One Square Metre	
23	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300mm or more (thickness to be specified by the manufacturer), of 1stquality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4(1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete.	6.00		One Square Metre	

24	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
a	75 mm diameter	6.00		One Running Metre	
b	110 mm diameter	6.00		One Running Metre	
25	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge.	5.00		One Square Metre	
26	12 mm cement plaster of mix :				
a	1:6 (1 cement: 6 coarse sand)	6.00		One Square Metre	
27	15 mm cement plaster on rough side of single or half brick wall of mix :				
a	1:6 (1 cement: 6 coarse sand)	4.00		One Square Metre	
28	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer, of required shade and colour all complete :				
a	New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre	40.00		One Square Metre	
29	Finishing walls with Acrylic Smooth exterior paint of required shade :				
a	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	20.00		One Square Metre	
30	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
a	Two or more coats on new work.	10.00		One Square Metre	
31	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				

a	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	12.00		One Square Metre	
32	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade.				
a	Old work (one or more coats)	25.00		One Square Metre	
33	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
a	One or more coats on old work.	18.00		One Square Metre	
34	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-harge.				
a	With cement mortar 1:4 (1cement: 4 coarse sand).	4.00		One Square Metre	
35	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty:				
a	Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm).	2.00		One Square Metre	
36	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	8.00		Each	
37	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls and floors wherever required :				
a	W.C. pan with ISI marked white solid plastic seat and lid	1.00		Each	
38	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink without drain board				
i	610x460 mm bowl depth 200 mm.	2.00		Each	

39	Providing and fixing white vitreous china pedestal type (European type/ wash down type) water closet pan.	1.00		Each	
40	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to Eureopean type W.C. of quality and make as approved by Engineer - in - charge.	2.00		Each	
41	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete.				
a	10 litre capacity - White	2.00		Each	
42	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete :				
a	White solid plastic seat with lid	2.00		Each	
43	Providing and fixing G.I. inlet connection for flush pipe connecting with W.C. pan.	2.00		Each	
44	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm or 340x410x265 mm sizes respectively.	1.00		Each	
45	Providing and fixing white vitreous china wash basin including making all connections but excluding the cost of fittings :				
a	Flat back wash basin of size 550x400 mm.	2.00		Each	
46	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe				
i	32 mm dia	6.00		Each	
47	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :				
a	Rectangular shape 453x357 mm	1.00		Each	
48	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour.				
a	Waste coupling 38 mm dia of 83 mm length and 77 mm breadth, weighing not less than 60 gms.	4.00		Each	
49	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
a	15 mm nominal outer dia. Pipes.	6.00		One Running Metre	
b	20 mm nominal outer dia. Pipes.	6.00		One Running Metre	

50	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. : Internal work – Exposed on wall.				
a	15 mm dia. nominal bore	6.00		One Running Metre	
b	20 mm dia. nominal bore	6.00		One Running Metre	
c	25 mm dia. nominal bore	6.00		One Running Metre	
51	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. : External work				
a	32 mm dia. nominal bore	3.00		One Running Metre	
b	40 mm dia. nominal bore	3.00		One Running Metre	
52	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :				
a	25 mm nominal bore	2.00		Each	
b	20 mm nominal bore	2.00		Each	
c	32 mm nominal bore.	1.00		Each	
d	40 mm nominal bore	1.00		Each	
53	Providing and fixing uplasticised PVC connection pipe with brass unions : 45 cm length				
i	15 mm nominal bore	6.00		Each	
54	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work)				
a	15 mm nominal bore	2.00		Each	
b	20 mm nominal bore	2.00		Each	
c	25 mm nominal bore	2.00		Each	
d	32 mm nominal	1.00		Each	
e	40 mm nominal bore	1.00		Each	
55	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	500.00		One Litre	
56	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931:				
a	15 mm nominal bore.	2.00		Each	
57	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.				
a	15 mm nominal bore	2.00		Each	

58	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 :				
a	15mm nominal bore	2.00		Each	
59	Providing and fixing PTMT bib cock of approved quality and colour.				
a	15mm nominal bore, 90 mm long. Weighing not less than 93 gms.	4.00		Each	
60	Providing and fixing PTMT pillar cock of approved quality and colour .				
a	15mm nominal bore, 125 mm long foam flow. Weighing not less than 120 gms.	2.00		Each	
61	Providing and fixing PTMT grating of approved quality and colour. Circular type.				
i	100 mm nominal dia.	4.00		Each	
62	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball.				
a	15 mm nominal bore, 105 mm long. Weighing not less than 138 gms.	6.00		Each	
63	Providing and fixing PTMT angle stop cock 15 mm nominal bore. Weighing not less than 85 gms.	2.00		Each	
64	Making chases up to 7.5x7.5 cm in walls including making good and finishing with matching surface after housing G.I. pipe etc.	6.00		One Running Metre	
65	Supplying of unskilled labour for miscellaneous maintenance works as per direction of Engineer-in-charge.	20.00		per day	
66	Providing and fixing double scaffolding system for repair works on the exterior/interior side or as required, upto four storey height made with bamboos 1.50 m c/c horoizontal and vertical bamboos along with challies tied with ropes & wires with suitable climbing ladders and working platforms, including, maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc. wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge .Note:- (1) The elevational area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works.	50.00		One Square Metre	
67	Hiring electic welding machine at site including cost of operator and electrodes as per the direction of E-in-c.	2.00		Each Job	
68	Providing and fixing PVC sheet with adhesive / screws, nails at back of flush door shutters as per direction of Engineer-in-charge.	1.00		One Square Metre	
69	Providing and fixing wire mesh of average width of aperture 1.40 mm and nominal diametre of wire 0.63 mm in wooden doors and windows with wooden fillets complete as per direction of Engineer-in-charge	2.00		One Square Metre	

70	Repair of brass/CP brass bib cock, stop cock, pillar cock etc by replacement of washers etc as per direction of Engineer-in-charge.	4.00		Each	
71	Supplying of spindles of CP brass bib cock, pillar cock, angle cock etc of approved quality	2.00		Each	
72	Providing and fixing 15 mm nominal bore GI socket, elbow, tee and nipple of approved quality	12.00		Each	
73	Providing and fixing PVC tank cover of approved quality as per direction of Engineer-in-charge.	3.00		Each	
74	Removal of chokage/leakage of floor traps, P traps, C.I. pipe etc and applying Dr Fixit wherever required as well as diposal of rubbish complete as per direction of Engineer-in-charge.	15.00		Each Job	
75	Cleaning of manhole including connecting sewerline by complete removal of rubbish etc and its disposal complete as per the direction of the Engineer-in-Charge.	15.00		Each Job	
76	Removal of sludge by mechanical means from septic tank and cleaning the same in land and around with water and disposal of sludge out side the compound at the authorized municipal dump or out of the township complete as per the direction of the Engineer-in-Charge.				
a	upto 12cum sludge capacity	1.00		Each	
77	Credit of old unservicable material obtained during dismantling				
a	wooden door and window of size up to 3 sqm	4.00		Each	
b	Mild steel sections , G.I. pipes etc	5.00		One Kilogram	
c	Brass/CP brass bib cock, stop cock, pillar cock, gate valve etc	6.00		Each	
d	500 litre PVC water storage tank	1.00		Each	
78	Refixing of dismembered aluminium partition, glass panes and particle board in the required new position,(excluding doors & windows) making into required shape & size as per site conditions including cost of rubber gasket,cleats, labour steel screws,etc. wherever required all complete, and as per the direction of Engineer-in Charge.	15.00		One Square Metre	

Executive Engineer (C)
BSNL Civil Division,
Haldwani